# BRUHAT BANGALORE MAHANAGARA PALIKE

## YELAHANKA ZONE

**Office of the Executive Engineer**
**Electrical Division, Yelahanka Zone**
**Bruhath Bengaluru Mahanagara Palike**

## "Schedule-B"

**Name of Work :-** Operation and Maintenance of street light fittings in Kuvempunagar ward no.14 Package Y-14 of Yelahanka Zone for the Period (10 Months).

**Job Code :** **P-Code: P0300**

**Estimat Amount: 38.50 Lakhs** **TS No:**

| Sl. No | Description Of Work | Unit | Qty | Quoted Rates | In words |
|---|---|---|---|---|---|
| 1 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **36/40 watt fluoroscent tube light street lighting systems.** | Each | 10 | 426.00 | Four Hundred Twenty Six Rupees |
| 2 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **125 watt HPMV park lighting systems.** | Each | 41 | 554.00 | Five Hundred Fifty Four Rupees |
| 3 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **250 watt HPSV street lighting systems.** | Each | 3073 | 792.00 | Seven Hundred Ninety Two Rupees |
| 4 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **400 watt HPSV street light/high mast lighting systems.** | Each | 88 | 854.00 | Eight Hundred Fifty Four Rupees |

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-92

| | | | | | |
|---|---|---|---|---|---|
| 5 | Operation and Maintenance of LED street lighting system including replacement of damaged/failed /fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **24 to 45 watt LED street lighting System.** | Each | 22 | 622.00 | Six Hundred Twenty Two Rupees |
| 6 | Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **50 to 72 watt LED street lighting systems.** | Each | 238 | 815.00 | Eight Hundred Fifteen Rupees |
| 7 | Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **90 watt LED street lighting systems.** | Each | 512 | 990.00 | Nine Hundred Ninety Rupees |
| 8 | Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **200 to 300 watt LED street lightingsystems.** | Each | 6 | 1000.00 | One Thousand Rupees |

I am prepared to take up the above work at rates quoted in the Schedule 'B'

**Contractor**

**EXECUTIVE ENGINEER (ELEC)**
**BBMP, Yelahanka Zone**